

ADDENDUM No. 3

DATE: April 5th, 2023

PROJECT: City of Sycamore
Well #7 Radium Treatment Improvements

PROJECT NUMBER: COS-008

OWNER: City of Sycamore

ENGINEER: Trotter and Associates, Inc.
40W201 Wasco Road, Suite D
St. Charles, Illinois 60175

TO: Prospective Bidders

The Addendum forms a part of the Contract Documents and modifies the Bidding Documents dated February 21st, 2023, with amendments and additions noted below.

Acknowledge receipt of this Addendum in the space provided on the Proposal Form. Failure to do so may disqualify the Bidder.

This Addendum consists of one (1) page and no attachments for a total addendum package of one (1) page. This is intended to be the final Addendum; no further questions will be answered.

Questions & Clarifications

1. The plans indicate that site piping as well as interior piping shall be CL53 ductile iron, but the specifications indicate CL52. Which should hold?

Response: Thickness Class 52 (CL52) shall be acceptable for the project.

2. What is the approximate depth of the proposed valve vault east of the existing Well Pump House?

Response: The existing water main to be connected to is anticipated to be approximately 6'-10" below grade. The interior bottom of the vault is required to be 18" below the bottom of pipe.

3. Will a geotechnical engineer be required to be on site for testing during the unsuitable soils undercut beneath the proposed Treatment Building? If so, who will be responsible for the cost of testing?

Response: A geotechnical engineer shall be present during the excavation associated with "Allowance Item #4 Subgrade Undercut" to determine the exact limits of required removal. As with other inspections required by the specifications, the Contractor shall be responsible for this cost.

THIS ADDENDUM IS HEREBY MADE PART OF THE CONTRACT DOCUMENTS AND SHALL BE NOTED ON THE PROPOSAL.

END ADDENDUM NO. 3